



SHEET INDEX	
TITLE SHEET	1
EXISTING CONDITIONS	2
STORM WATER DRAINAGE PLAN	3
PROFILES AND DETAILS	4
ADDITIONAL DETAILS	5



SITE PLAN FOR THE LANDS OF ACCOMACK-NORTHAMPTON TRANSPORTATION DISTRICT COMMISSION



OWNERS/DEVELOPER'S CERTIFICATE

AS THE PROPERTY OWNER/DEVELOPER, I AM IN FULL AGREEMENT WITH THIS SITE PLAN SUBMITTED HERewith, AND I AM RESPONSIBLE FOR THE COMPLETION OF THE IMPROVEMENTS AS SHOWN ON THE APPROVED SITE PLAN, AND I UNDERSTAND THAT I CANNOT ALLOW THE PROPERTY OR BUILDINGS TO BE OCCUPIED UNTIL A CERTIFICATE OF USE AND OCCUPANCY HAS BEEN ISSUED BY THE DEPARTMENT OF DEVELOPMENT, REVIEW AND PERMITTING.


Phil Thompson
PHIL THOMPSON
DATE: 11/7/2022

APPROVED

RESPONSIBLE LAND DISTURBER INFORMATION

THE PERSON IDENTIFIED BELOW IS DESIGNATED AS THE RESPONSIBLE LAND DISTURBER WHO WILL BE IN CHARGE OF AND RESPONSIBLE FOR CARRYING OUT THE LAND DISTURBING ACTIVITY ASSOCIATED WITH THIS PROJECT. THIS PERSON MEETS THE APPLICABLE REQUIREMENTS OF VIRGINIA CODE SECTION 10.1-553 AND 10.1-566 BY VIRTUE OF THE FOLLOWING:

PROJECT NAME: _____
PROJECT LOCATION: _____
TAX MAP #: _____
CERTIFICATE NUMBER: _____
TYPE OF CERTIFICATE: _____ **EXP DATE:** _____
LICENSE HOLDER NAME: _____
PHONE NUMBER: () _____
COMPANY: _____
ADDRESS: _____
SIGNATURE: _____ **DATE:** _____



- LEGEND**
- ⊙ - OUTLET PROTECTION
 - ⊙ - ROCK CHECK DAM
 - ⊙ - SILT FENCE
 - - SILT FENCE
 - - LIMITS OF DISTURBANCE
 - ⊙ - POND AERATOR
 - ⊙ - WOOL GRASS
 - ⊙ - POND WEED
 - ⊙ - SEDGE
 - - RUNOFF DIRECTION
 - - POSTDEVELOPMENT PAVED AREA
 - - EXISTING PAVED AREA
 - - GRAVEL
 - - ROOF/BUILDING TOP AREA

- NOTES:**
- OWNER CONTACT
 - NAME: PHIL THOMPSON
 - WORK PHONE: 540-292-1668
 - MAILING: 9VA025-870-0, THIS PROJECT DOES NOT MEET LINEAR DEVELOPMENT CRITERIA
 - P.O. BOX 2665
PURCELLVILLE, VA 20134
 - E-MAIL: PHIL@VATRANSIT.ORG
 - PRECONSTRUCTION
 - VERIFY ALL UTILITIES AND STRUCTURES THAT ARE AFFECTED BY CONSTRUCTION.
 - CONTACT AND SCHEDULE MRS. UTILITY (1-800-441-8355)
 - SITE ATTRIBUTES
 - TAX MAP 93(A)
 - PARCEL 87
 - DEED REF. 634/298
 - SITE TOTAL AREA: 126,592.55SQFT (2.91AC)
 - SITE TOTAL AREA: 33,751sqft (0.74ac)
 - ROOF/BUILDING: 4,918sqft
 - PAVED SURFACE: 22,794sqft
 - POST-DEVELOPMENT IMPERVIOUS: 35,968sqft (0.83ac)
 - ROOF/BUILDING: 4,918sqft
 - PAVED SURFACE: 32,546sqft
 - LIMITS OF DISTURBANCE: 40,294sqft (0.925ac)
 - WHEREAS 9VA025-870-0, THIS PROJECT DOES NOT MEET LINEAR DEVELOPMENT CRITERIA
 - ENVIRONMENTAL
 - THE SITE CONTAINS NO KARST FORMATIONS
 - PER ACCOMAP, ON 4/5/2022, SITE IS NOT LOCATED WITHIN A CAPA RESOURCE PROTECTION AREA
 - SITE SOIL COMPOSITIONS
 - 100% Nmc NIMMO SANDY LOAM, 0 TO 2 PERCENT SLOPES
 - PER ACCOMAP, ON 4/5/2022, THE SITE CONTAINS NO WETLANDS


Cew
RECEIVED
NOV 09 2022
ACCOMACK COUNTY
DEPARTMENT OF
ENVIRONMENTAL PROGRAMS

Curve Data
Rad = 318.10'
Arc = 492.81'
Δ = 86°45'49"
ChL = 444.98'
ChB = N 25°50'44" E

PROFESSIONAL ENGINEER'S CERTIFICATE

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF VIRGINIA, LICENSE 13087, EXPIRATION DATE: 06/30/2024.

George E. Young, III
GEORGE E. YOUNG, III
PROFESSIONAL ENGINEER
DATE: NOV 03 2022





REVISIONS:
ADDED HATCHING TO LEGEND, SITE DEV. CONTEXT VIEW (SHEET 1)
10/4/2022 - UPDATED PER 9/12/2022 COMMENTS

GEY
GEORGE E. YOUNG, III, P.C.
ENGINEERS & SURVEYORS
1603 MARKET STREET
POCCOMOKE MARYLAND 21851
PHONE: (410)-957-2149
FAX: (410)-957-2928

PROJECT NUMBER: **V21300-B**
REVISION: **B**
SHEET: **1 of 5**

NOV 03 2022
PROFESSIONAL ENGINEER

EXISTING CONDITIONS FOR THE LANDS OF ACCOMACK-NORTHAMPTON TRANSPORTATION DISTRICT COMMISSION



LEGEND

- ⊙ - OUTLET PROTECTION
- ⊕ - ROCK CHECK DAM
- ⊖ - SILT FENCE
- ⊗ - SILT FENCE
- - LIMITS OF DISTURBANCE
- ⊙ - POND AERATOR
- ⊙ - WOOL GRASS
- ⊙ - POND WEED
- ⊙ - SEDGE
- ➔ - RUNOFF DIRECTION
- - POSTDEVELOPMENT PAVED AREA
- - EXISTING PAVED AREA
- - GRAVEL
- - ROOF/BUILDING TOP AREA

- NOTES:**
1. OWNER CONTACT
 - 1.1 NAME: PHIL THOMPSON
 - 1.1 WORK PHONE: 540-292-1668
 - 1.2 MAILING: P.O. BOX 2665 PURCELLVILLE, VA 20134 E-MAIL: PHIL@VATRANSIT.ORG
 2. PRECONSTRUCTION
 - 2.1 VERIFY ALL UTILITIES AND STRUCTURES THAT ARE AFFECTED BY CONSTRUCTION.
 - 2.2 CONTACT AND SCHEDULE MRS. UTILITY (1-800-441-8355)
 3. SITE ATTRIBUTES
 - 3.1 TAX MAP 93(A)
 - 3.2 PARCEL 87
 - 3.3 DEED REF. 634/298
 - 3.4 SITE TOTAL AREA: 126,592.55SQFT (2.91AC)
 - 3.5 EXISTING IMPERVIOUS: 33,751sqft (0.74ac)
 - 3.5.1 ROOF/BUILDING: 4,918sqft
 - 3.5.2 PAVED SURFACE: 22,794sqft
 - 3.6 POST-DEVELOPMENT IMPERVIOUS: 35,968sqft (0.83ac)
 - 3.6.1 ROOF/BUILDING: 4,918sqft
 - 3.6.2 PAVED SURFACE: 32,546sqft
 - 3.7 LIMITS OF DISTURBANCE: 40,294sqft (0.925ac)
 - 3.8 WHEREAS 9VAC25-870-10, THIS PROJECT DOES NOT MEET LINEAR DEVELOPMENT CRITERIA
 4. ENVIRONMENTAL
 - 4.1 THE SITE CONTAINS NO KARST FORMATIONS
 - 4.2 PER ACCOMP, ON 4/5/2022, SITE IS NOT LOCATED WITHIN A CAPA RESOURCE PROTECTION AREA
 - 4.3 SITE SOIL COMPOSITIONS
 - 4.3.1 100% Nmic NIMMO SANDY LOAM, 0 TO 2 PERCENT SLOPES
 - 4.4 PER ACCOMP, ON 4/5/2022, THE SITE CONTAINS NO WETLANDS


REVISIONS:

5/8/2022	- UPDATES PER 7/21/2022 COMMENTS
10/4/2022	- UPDATED PER 9/12/2022 COMMENTS


GEY
GEORGE E. YOUNG, III, P.C.
 ENGINEERS & SURVEYORS
 1603 MARKET STREET
 POCOMOKE MARYLAND 21851
 PHONE: (410)-957-2149
 FAX: (410)-957-2928

PROJECT NUMBER
V21300-B
REVISION
B
SHEET
2 of 5

NOV 03 2022
 PROFESSIONAL ENGINEER












PROFILES AND DETAILS
FOR THE
LANDS OF
ACCOMACK-NORTHAMPTON
TRANSPORTATION DISTRICT COMMISSION



LEGEND

 - CUT
 - FILL
 - KEEP







REVISIONS:
 8/8/2022 - UPDATES PER 7/21/2022 COMMENTS
 10/4/2022 - UPDATED PER 9/12/2022 COMMENTS

GEY
 GEORGE E. YOUNG, III, P.C.
 ENGINEERS & SURVEYORS
 1603 MARKET STREET
 POCOMOKE MARYLAND 21851
 PHONE: (410)-957-2149
 FAX: (410)-957-2928

DRAWN BY: CED
 DATE DRAWN: 04/04/2022
 DESIGNED BY: CED
 CHECKED BY: GEY
 CADD DWG: V21300-B
 DATE PLOTTED: 10/4/2022

PROJECT NUMBER: V21300-B
 REVISION: B
 SHEET: 4 of 5


NOV 03 2022
 PROFESSIONAL ENGINEER



ADDITIONAL DETAILS
FOR THE
LANDS OF
ACCOMACK-NORTHAMPTON
TRANSPORTATION DISTRICT COMMISSION


STANDARD EROSION & SEDIMENT CONTROL NOTES

1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (3RD EDITION, 1992) AND THE VIRGINIA EROSION AND SEDIMENT CONTROL REGULATIONS (4VAC50-30).
2. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION. THE NAME OF THE RESPONSIBLE LAND DISTURBER MUST BE PROVIDED TO THE PLAN-APPROVING AUTHORITY PRIOR TO ACTUAL ENGAGEMENT IN LAND-DISTURBING ACTIVITY SHOWN ON THE APPROVED SITE PLAN. IF THE NAME IS NOT PROVIDED PRIOR TO ENGAGING IN THE LAND-DISTURBING ACTIVITY THE PLAN'S APPROVAL WILL BE REVOKED.
3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN AND THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.
6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED, AFTER WHICH, UPON APPROVAL OF THE PLAN APPROVING AUTHORITY, THE CONTROLS SHALL BE REMOVED. TRAPPED SEDIMENT AND THE DISTURBED SOIL AREAS RESULTING FROM THE REMOVAL OF TEMPORARY MEASURES SHALL BE SEDIMENT AND THE DISTURBED SOIL AREAS RESULTING FROM THE REMOVAL OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION AND SEDIMENTATION.
8. DURING DEWATERING OPERATIONS, WATER SHALL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
9. THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES AT LEAST EVERY TWO (2) WEEKS AND IMMEDIATELY AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY. THE RESPONSIBLE LAND DISTRIBUTOR ASSOCIATED WITH THIS PROJECT SHALL MAINTAIN WRITTEN MONITORING REPORTS ON-SITE AND PROVIDE TO THE DCR STORMWATER COMPLIANCE SPECIALIST UPON REQUEST.
10. THE CONTRACTOR IS RESPONSIBLE FOR THE DAILY REMOVAL OF SEDIMENT THAT HAS BEEN TRANSPORTED ONTO A PAVED OR PUBLIC ROAD SURFACE.
11. SEEDING OPERATIONS SHALL BE INITIATED WITHIN 7 DAYS AFTER REACHING FINAL GRADE OR UPON SUSPENSION OF GRADING OPERATIONS FOR ANTICIPATED DURATION OF GREATER THAN 30 DAYS OR UPON COMPLETION OF GRADING OPERATIONS FOR A SPECIFIC AREA.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SURFACE AND AIR MOVEMENT OF DUST FROM EXPOSED SOILS WHICH MAY PRESENT HEALTH HAZARDS, TRAFFIC SAFETY PROBLEMS, OR HARM ANIMAL OR PLANT LIFE.
13. A VIRGINIA STORMWATER MANAGEMENT PERMIT (VSM) FOR THE DISCHARGE OF STORMWATER FROM CONSTRUCTION ACTIVITIES IS REQUIRED FOR THE PROPOSED PROJECT AS THE DISTURBANCE IS GREATER THAN 1 ACRE. A VSM IS ALSO REQUIRED FOR PROJECTS DISTURBING TWO THOUSAND FIVE HUNDRED SQUARE FEET (2,500sqft) OR GREATER IN A DESIGNATED CHESAPEAKE BAY.
14. LIMITS OF SOIL DISTURBANCE, GRADING, PAVING, AND/OR SEEDING/STABILIZATION INCLUDE ALL CONSTRUCTION AREAS AND ADJACENT SITES WITHIN THE PHASE LIMITS AS SHOWN.
15. EACH AREA SHALL BE PERMANENTLY OR TEMPORARILY STABILIZED WHEN SITE DEVELOPMENT WORK, GRADING OR OTHER EARTH DISTURBANCE ACTIVITIES CEASE TO BE CONTINUOUS FOR MORE THAN SEVEN (7) DAYS.
16. DURING THE LAYOUT OF THE SEDIMENT CONTROL DEVICES SHOWN ON PLANS, FIELD ADJUSTMENTS SHALL BE MADE TO INSURE THAT PROPER PLACEMENT HAS BEEN MADE TO ARREST AND CONTROL ANY SEDIMENT THAT COULD LEAVE THE CONSTRUCTION SITE.
17. ALL OUTFALLS ARE TO BE PROTECTED FROM EROSION VELOCITIES WITH RIP-RAP.
18. PUBLIC ROADS AND OTHER RIGHT-OF-WAYS SHALL BE KEPT FREE OF SEDIMENT DEPOSITS LEFT FROM HEAVY TRUCK TRAFFIC LEAVING THE CONSTRUCTION SITE.
19. PERMANENT STABILIZATION OF ALL AREAS NOT TO BE SODED OR PAVED SHALL BE SEEDED AND MULCHED IN ACCORDANCE WITH VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.
20. IMMEDIATELY AFTER FINAL GRADES ARE OBTAINED, ALL AREAS TO BE PAVED, SHALL BE PAVED.
21. FOLLOWING INITIAL SOIL DISTURBANCE OR REDISTURBANCE, PERMANENT OR TEMPORARY SITE STABILIZATION SHALL BE COMPLETED WITHIN:
 - 21.1. SEVEN (7) CALENDAR DAYS AS TO THE SURFACE OF ALL PERIMETER CONTROLS, DIKES, SWALES, DITCHED, PERIMETER SLOPES, AND ALL SLOPES GREATER THAN 3 HORIZONTAL TO 1 VERTICAL (3:1)
 - 21.2. SEVEN (7) DAYS AS TO ALL OTHER UNDISTURBED OR GRADED AREAS ON THE PROJECT SITE.
22. ALL STOCKPILES THAT ARE TO BE LEFT UNDISTURBED FOR THREE (3) WEEKS OR LONGER SHALL IMMEDIATELY AFTER PILING BE FERTILIZED, LIMED AND SEEDED WITH ANNUAL RYE GRASS AT A RATE OF ONE POUND (1lb) PER ONE THOUSAND SQUARE FEET (1,000sqft)
23. ALL TEMPORARY STABILIZATION SHALL BE AS FOLLOWS:
 - 23.1. PULVERIZED DOLOMITIC LIMESTONE APPLIED AT A RATE OF TWO THOUSAND POUNDS (2,000lbs) PER ACRE OR FORTY SIX POUNDS (46lbs) PER ONE THOUSAND SQUARE FEET (1,000sqft)
 - 23.2. FERTILIZER (5-5-5) APPLIED AT A RATE OF FIVE HUNDRED POUNDS (500lbs) PER ACRE OR ELEVEN AND A HALF POUNDS (11.5lbs) PER ONE THOUSAND SQUARE FEET (1,000sqft)
 - 23.3. RYE GRASS APPLIED AT A RATE OF FORTY POUNDS PER ACRE (40lbs/ac), FERTILIZER (5-10-10) AND MULCH WITH STRAW AT ONE AND A HALF TONS PER ACRE (1.5t/ac)
24. ANYTIME AN EROSION SEDIMENT PROBLEM OCCURS THE PROMPT AND NECESSARY MEASURES WILL BE TAKEN TO CORRECT IT BY THE CONTRACTOR.



- Maintenance**
1. Silt fences shall be inspected immediately after each rainfall and at least daily during prolonged rainfall. Any required repairs shall be made immediately.
 2. Close attention shall be paid to the repair of damaged silt fence resulting from end runs and undercutting.
 3. Should the fabric on a silt fence decompose or become ineffective prior to the end of the expected usable life and the barrier still be necessary, the fabric shall be replaced promptly.
 4. Sediment deposits should be removed after each storm event. They must be removed when deposits reach approximately one-half the height of the barrier.
 5. Any sediment deposits remaining in place after the silt fence is no longer required shall be dressed to conform with the existing grade, prepared and seeded.

- TYPICAL SEQUENCE OF CONSTRUCTION**
1. CLEAR AND GRUB SITE FOR PERIMETER CONTROLS ONLY.
 2. INSTALL STABILIZED CONSTRUCTION ENTRANCE.
 3. INSTALL SILT FENCE IN ITS ENTIRETY.
 4. CONSTRUCT STORMWATER MANAGEMENT POND IN IT'S ENTIRETY.
 5. STRIP TOPSOIL FROM SITE WITHIN THE LIMITS OF DISTURBANCE AND STORE IN DESIGNATED STOCKPILE AREA.
 6. FOLLOWING INITIAL SOIL DISTURBANCE AND REDISTURBANCE, DETAILS OF TEMPORARY OR PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN SEVEN CALENDAR DAYS ON ALL SURFACES OF PERIMETER CONTROLS, DIKES, SWALES, DITCHES, PERIMETER SLOPES AND ALL SLOPES STEEPER THAN THREE HORIZONTAL TO ONE VERTICAL (3:1).
 7. ROUGH GRADE PROPOSED BUILDING AND PROPOSED DRIVEWAY/PARKING SPACES IMPORTING MATERIAL AS NECESSARY FROM SITE OR OFF-SITE SOURCE PER PROPOSED GRADES PROVIDED TO CREATE POSITIVE DRAINAGE.
 8. FINAL GRADE PROPOSED BUILDING AREA AND PROPOSED DRIVEWAY/PARKING AREAS.
 9. STABILIZE ALL REMAINING DISTURBED AREAS WITH PERMANENT VEGETATION OR SITE SPECIFIC VEGETATION AS NOTED.
 10. WITHIN THE SEVEN DAYS FOLLOWING FINAL GRADING, ALL OTHER DISTURBED OR GRADED AREAS ON THE PROJECT WILL BE PERMANENTLY STABILIZED BY SEEDING OR MULCHING. PERMANENT MULCH CAN INCLUDE BUT IS NOT LIMITED TO STONE, GRAVEL, BLACKTOP OR CONCRETE SURFACING. IF CONSTRUCTION IS TEMPORARY STOPPED ON A PROJECT SITE FOR MORE THAN SEVEN DAYS, ALL GRADED AREAS SHALL BE STABILIZED. THE REQUIREMENTS OF THIS SUBPARAGRAPH DO NOT APPLY TO THOSE AREAS WHICH ARE SHOWN ON THE PLAN AND ARE CURRENTLY BEING USED FOR MATERIAL STORAGE, OR FOR THOSE AREAS ON WHICH ACTUAL CONSTRUCTION ACTIVITIES ARE CURRENTLY BEING PERFORMED OR TO INTERIOR AREAS OF A SURFACE MINE SITE WHERE STABILIZATION MATERIAL WOULD CONTAMINATE THE RECOVERABLE RESOURCE.
 11. REMOVE ALL EROSION AND SEDIMENT CONTROL MEASURES AS DIRECTED BY THE INSPECTOR.
 12. ALL MAINTENANCE OF THE FINAL SITE SHALL BE CONTROLLED BY THE SITE OWNER.



TEMPORARY SEEDING SUMMARY

HARDNESS ZONE (FROM FIGURE B.3) 7A SEED MIXTURE (FROM TABLE B.1)				FERTILIZER RATE (10-20-20)	LIME RATE
NO.	SPECIES	RATE [LBS/AC]	SEEDING DATES	DEPTH [IN]	
1	ANNUAL RYEGRASS	40	FEB. 15TH TO APRIL 30TH AUG. 1ST TO NOV. 30TH	1 2	436 LB/AC (10LB/1000SF) 90LB/AC (2LB/1000SF)

PERMANENT SEEDING SUMMARY

HARDNESS ZONE (FROM FIGURE B.3) 7A SEED MIXTURE (FROM TABLE B.1)				FERTILIZER RATE (10-20-20)			LIME RATE
NO.	SPECIES	RATE [LBS/AC]	SEEDING DATES	DEPTH [IN]	N	P ₂ O ₅	K ₂ O
8	TALL FESCUE	100	FEB. 15TH TO APRIL 30TH MAY 1ST TO NOV. 30TH	1/4 - 1/2	1LB/1000SF	90LB/AC (2LB/1000SF)	90LB/AC (2LB/1000SF)
9	HARD FESCUE	40	FEB. 15 TO APRIL 30TH	1/4 - 1/2	45LB/AC (1LB/1000SF)	90LB/AC (2LB/1000SF)	90LB/AC (2LB/1000SF)

REVISIONS:
8/8/2022 - UPDATES PER 7/21/2022 COMMENTS

DRAWN BY: CED
DATE DRAWN: 04/04/2022
DESIGNED BY: CED
CHECKED BY: GEY
CADD DWG: V21300-B
DATE PLOTTED: 10/4/2022

GEY
ENGINEERS & SURVEYORS
1603 MARKET STREET
POCOCKE MARYLAND 21851
PHONE: (410)-957-2149
FAX: (410)-957-2928

PROJECT NUMBER
V21300-B
REVISION
B
SHEET
5 of 5

NOV 03 2022
PROFESSIONAL ENGINEER